

Date: February 13, 2017



Salida Scout Hut Building Renovation Project Addendum #2, dated 02-13-17

1. Please provide additional general clarifications regarding the project's Fire Alarm System

- The fire alarm system is intended to be installed as a design/ build, meeting the requirements of NFPA 72 (the "C" referenced in the specification is incorrect)
- Upon receipt of contract, the successful bidder shall prepare fire alarm plans in accordance with the requirements of NFPA 72 and the requirements of the City of Salida Fire Department (719) 539-2212
- The fire alarm plans shall be submitted for review to the City of Salida Fire Department/ Fire Chief
- Upon receiving approval from the City of Salida Fire Department, the plans shall be submitted to the Architect for architectural/ engineering review
- The fire alarm sub-contractor shall be approved by or shall have supervision by the manufacture of the fire alarm system equipment being installed
- The fire alarm panel is to be installed on the south wall of the west entry lobby
- The fire alarm system shall be monitored with a leased line direct to the Salida Fire Department Central Dispatch
- Final testing and commissioning of the fire alarm system shall be done under the supervision of the Salida Fire Department

Please note that Paragraph 1.03.2C in the NFPA 72 is not applicable. The Scout Hut project does not include a fire sprinkler system

End of Addendum #2, 02-13-17